BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

Name of Work: Maintenance of Borewell in Ward No.14 Bagalagunte T.Dasarahalli Sub Division.

Sl.No	Description of work	Unit	Qty	Rates to be Quoted	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Supply and delivery at site brand new Texmo / Innoval / Lubi / Sabar / Atalanta / Calamal / waterman / Radha make suitable vertical installation in 150mm dia. Borewells comprising of single stage or miultistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction mortor suitable for operation of 3Ph., 50Hz. 380/44 volts AC supply fitted with required accessories such as suction. casing, suction strainers, sand guard Non return valve etc., complete the pump and motor shall form an integral unit with all the required fittings 15HP 30 stageComplete as per specifications.				
a	15HP 30 stage	No	2.00	71265.00	Rupees Seventy One Thousand Two
2	Supplying and Drawing 3 core Flat PVC Shalted Submersible Pump Cable Manufactured with Electrolytic Grade Copper with Flexible copper conductor to table 3 class 5 of IS 8130-1984 and Virgen PVC insulation and Sheeated Suitable for working Voltage Upto 1100 Volts Complete as per specifications.	Mtrs	1500.00	159.50	Rupees One Hundred Fifty Nine and Fifty Paise Only
3	Supplying and fixing 50mm Non Return Vavle of vertical type of approved make including cost of all materials labour HOM of equipment with all leads Complete as per specifications.	Nos	10.00	1600.00	Rupees One Thousand Six Hundred Only
4	Supplying and fixing 50mm GM Gae Vavle Complete as per specifications.	Nos	8.00	1145.00	Rupees One Thousand One Hundred Forty Five Only
5	Supplying and fixing 160mm Borewell cap with clampset Complete as per specifications.	Nos	5.00	690.00	Rupees Six Hundred Ninety Only
6	Supplying and fixing 50mm GI Union Complete as per specifications.	Nos	5.00	223.70	Rupees Two Hundred Twenty Three and Seventy Paise Only
7	Supplying and fixing 50mm GI Elbow Complete as per specifications.	Nos	20.00	111.80	Rupees One Hundred Eleven and Eighty Paise Only

Signature of the Contractor

Technical Manager(TM-2)

Executive Engineer